



DETAIL 1 (EXISTING)

SCALE: NOT TO SCALE



DETAIL 2 (NEW)

SCALE: NOT TO SCALE

- NOTES:

1. FIELD TO RELOCATE ALL EXISTING EQUIPMENT SHOWN IN AND BELOW THIS RACK. MOUNT THE NETWORK CONNECTOR, PRIMARY RECEIVER AND EOL'S IN THE RACK SIMILAR TO SECTION "A-A" THIS DRAWING.
2. NOT USED
3. NOT USED
4. INSTALL THE "MXL" COMPUTER (NETWORK COMMAND CENTER-NCC), MONITOR, KEYBOARD, MOUSE, ETC, IN THIS RACK. RELOCATE ALL EXISTING EQUIPMENT. CONNECT THE "MXL" TO THE "NCC".
5. CONNECT PRINTERS TO EXISTING RECEPTACLES. AND CONNECT TO PRINTER PORTS OF BOTH COMPUTER SYSTEMS WITH RIBBON CABLES.
6. CONTACT Ed Ritenour, EXTENSION 5754, FOR 100 PAIR, #24 AWG CABLE.
7. CONVERT EXISTING "MX-203" TERMINAL ASSEMBLY CABINET TO TERMINAL BOX "TB-01-48". DISCONNECT AND REMOVE EXISTING SYSTEM 3 PANEL FAP-01-048.
8. RELOCATE MXL PANEL MXL-01-48 TO THE DISPATCH ROOM "102", AS SHOWN ON THIS DRAWING.

