



1 4TH LEVEL DEMOLITION PLAN - FIRE ALARM
1/8" = 1'-0"

KEY NOTES:

- CAREFULLY REMOVE INDICATED FIRE CALL BOX AND CONDUIT DROP. COMPLETE ALARM CIRCUIT TO PLACE SYSTEM BACK INTO SERVICE. PROVIDE TEMPORARY PLUG/CAP AT JUNCTION BOX. RETAIN FIRE CALL BOX FOR REINSTALLATION WHERE INDICATED.
- CAREFULLY REMOVE INDICATED SMOKE DETECTOR (AND CONDUIT IF EXPOSED). COMPLETE ALARM CIRCUIT TO PLACE SYSTEM BACK INTO SERVICE. PROVIDE TEMPORARY PLUG/CAP AT JUNCTION BOX. RETAIN SMOKE DETECTOR FOR REINSTALLATION WHERE INDICATED.
- REMOVE AND DISPOSE OF THE EXISTING HEAT DETECTOR. COMPLETE ALARM CIRCUIT TO PLACE SYSTEM BACK INTO SERVICE. PROVIDE COVER OVER BOX.
- CAREFULLY REMOVE INDICATED NOTIFICATION APPLIANCE. COMPLETE ALARM CIRCUIT TO PLACE SYSTEM BACK INTO SERVICE. PROVIDE TEMPORARY PLUG/CAP AT JUNCTION BOX. RETAIN NOTIFICATION APPLIANCE FOR REINSTALLATION WHERE INDICATED.
- TO THE EXTENT NECESSARY TO FACILITATE SEISMIC STRUCTURAL WORK ELEMENTS IN THIS AREA, REMOVE EXISTING CONDUIT AND SUPPORTS.