



1 P/A, TEL./COMM. & FIRE ALARM
E2.2 SCALE:

CONFORMED 6/17/99

Daniel, Mann, Johnson, & Mendenhall
530 Bush Street, Suite 900
San Francisco, CA 94108-3625
(415) 988-1373

1	AD	AM	JK	JK	3/14/99	50% SUBMITTAL
2	AD	AM	JK	JK	3/14/99	100% SUBMITTAL
3	CC	AM	JK	JK	3/14/99	100% SUBMITTAL CONSTRUCTION DOCUMENTS

SHEET NOTES:

- FOR LOCATION OF (E) PANELS, SEE DWG. E1.1.
- COORDINATE ALL P/A SYSTEM, TEL./COMM. SYSTEMS RELATED WORK WITH LBNL. CABLES, SPEAKERS, AND EQUIPMENT SHALL BE FURNISHED AND INSTALLED BY LBNL. ALL WIRING, TERMINATION AND CONNECTION ON THE PUBLIC ADDRESS AND TEL./COMM. SYSTEMS SHALL BE DONE BY OTHERS (LBNL).
- COORDINATE FIRE ALARM SYSTEM RELATED WORK WITH LBNL. PROVIDE CONDUIT AND WIRING. TERMINATIONS AND CONNECTIONS TO MAIN FACP SHALL BE DONE BY OTHERS (LBNL).
- UNLESS NOTED OTHERWISE, TEL./COMM. OUTLET BOX SHALL BE MOUNTED AT 1'-3" A.F.F. AND WALL MOUNTED SPEAKERS SHALL BE MOUNTED AT 10'-0" A.F.F.
- PROVIDE NYLON PULL STRING IN ALL EMPTY CONDUITS (C.O.).
- SEAL AND FLASH ALL PENETRATIONS IN EXTERIOR WALLS. SEE DWG. A7.2, DETAIL #3.

KEY NOTES:

- TO (E) FATC VIA (E) FA JUNCTION BOX LOCATED IN ROOM 140 PROVIDE 3'-0" OF WIRE SLACK IN THE FA BOX FOR FINAL TERMINATION & CONNECTION BY OTHERS (LBNL).
- NEW TEL./COMM. PULLBOX, 18"L x 12"W x 6"D, MOUNTED AT 8'-0" AFF.
- TEL./COMM. OUTLET BOX MOUNTED AT 3'-6" AFF.
- ROUTE CONDUIT TO NEW TEL./COMM. PULLBOX.
- DUCT SMOKE DETECTOR (DSD) IS FURNISHED AND INSTALLED BY MECHANICAL CONTRACTOR. THE DSD IS LOCATED ON THE MEZZANINE LEVEL. SEE DWG M2.2 FOR EXACT LOCATION.
- TO (N) TELEPHONE PULLBOX LOCATED IN SOUTHEAST CORNER OF B64.

BUILDING 64
HIGH BAY RENOVATION
P/A, TEL./COMM. & FIRE ALARM
UNIVERSITY OF CALIFORNIA LAWRENCE BERKELEY LABORATORY
FACILITIES DEPARTMENT

DESIGNED BY	A. DUNCAN	DATE	5/14/99
CHECKED BY	A. REYHER	DATE	5/14/99
APPROVED BY	J. KIM	DATE	5/14/99
DESIGN FILE PATH	000000338		
SCALE	AS NOTED		
DRAWING NO.	4B64E077	SHEET	E2.2
PROJECT NO.	FMB300		35 OF 41