

SEQUENCE OF OPERATIONS:

1. TSI 8650 WILL MODULATE FUME HOOD EXHAUST DAMPERS TO MAINTAIN EXHAUST AIR VELOCITY.
2. ROOM DIFFERENTIAL STATIC PRESSURE SENSOR SHALL MODULATE THE EXHAUST BYPASS DAMPER TO MAINTAIN ROOM AT $-0.02''$ W.C. STATIC PRESSURE RELATIVE TO THE CORRIDOR.
3. VERIFY THAT WHEN FUME HOOD SASH IS FULLY OPEN ROOM WILL MAINTAIN STATIC PRESSURE SETPOINT.
4. VERIFY THAT ROOM TEMPERATURE IS MAINTAINED W/(E) REHEAT CONTROL VALVE.
5. AIR VELOCITY THROUGH FUME HOOD SASH W/24" OPENING SHALL BE CONTROLLED TO 110 (+/-) 10 FPM.

| (N) F U M E H O O D S C H E D U L E | | | | |
|-------------------------------------|--|---|---|------------------------------------|
| ROOM | MODEL | UTILITIES | ELECTRICAL | DIMENSIONS |
| 246 | ALC 6' HOOD W/ RESTRICTED BYPASS VAV FUME HOOD, MOLDED EPOXY-RESIN LINER & COUNTER TOP, RIGHT-REAR CUP SINK, 2' FLAM CABINET, 2' CORROSIVE CABINET, & 2' SAA AREA. (MODIFY CONSTANT W/BYPASS EXHAUST TO VAV HOOD) | 1,320 CFM EXHAUST @ 110 FPM VELOCITY 1.0" WG TSP CA, ICW, & N | LIGHT & 120V GFI DUPLEX (REPLACE TSI 8610 W/ TSI 8650 MONITOR/CONTROLLER) FIELD INSTALL ONE FOUR-PLEX OUTLETS ON EITHER SIDE OF THE FUME HOOD | 72"W x 36"D x 90"H 1,200 POUNDS |

EXHAUST FAN SCHEDULE

| MARK | MFR. | MODEL | VOLTAGE | RPM | CFM | H.P. | T.S.P. | TYPE | OPER'G. WT. (LBS.) | SERVICE | NOTES |
|-----------|-----------|------------|---------|-------|-------|------|--------|-------------|--------------------|-----------|---|
| BL-XXX-XX | GREENHECK | 10-BISW-41 | 460 | 2,571 | 1,320 | 3/4 | 1.0 | CENTRIFUGAL | 200 | FUME HOOD | ALL STRUCTURAL STEEL PARTS PHOSPHATIZED AND COATED W/PERMATECTOR. |

LBNL STANDARD FUME HOOD SCHEDULE

UNIVERSITY OF CALIFORNIA LAWRENCE BERKELEY NATIONAL LABORATORY
FACILITIES DIVISION

| | |
|---------------|-------|
| DRAWN BY | DATE |
| CHECKED BY | |
| APPROVED BY | |
| CAD FILE PATH | |
| SCALE | NTS |
| DRAWING NO. | SHEET |
| H 1 2 8 | |
| PROJECT NO. | |