

NOTES:

- FLEXIBLE DUCTS ARE NOT PERMITTED UPSTREAM OF A VAV BOX
 PROVIDE 30" CLEAR SPACE AT THE CONTROL BOX FOR SERVICING



	27. Tarabar and Ta	
LBNL STANDARD	DRAWN BY	DATE
VAV BOX WITH REHEAT COIL	CHECKED BY	
	APPROVED BY	
	CAD FILE PATH	
	SCALE NTS	
UNIVERSITY OF CALIFORNIA LAWRENCE BERKELEY NATIONAL LABORATORY	DRAWING NO.	SHEET
FACILITIES DIVISION	H147	
TACILITIES DIVISION	PROJECT NO.	