DUCT–FREE MULTI–SPLIT AIR CONDITIONING UNIT SCHEDULE
AC–39–90

INDOOR AIR CONDITIONING UNIT		OUTDOOR AIR–COOLED CONDENSING UNIT	
(2) – CARRIER INDOOR CEILING MOUNTED FAN–COIL UNIT 40QKB024, 2 NOMINAL TONS 24,000 BTU/H COOLING, 800 CFM WITH PROGRAMMABLE THERMOSTAT AND REMOTE CONTROLLER W/ INDOOR UNIT.		OUTDOOR CONDENSING UNIT CARRIER 38HDS024–3 COMPRESSOR : R.L.A. =12.9, L.R.A. = 62.5 FAN MOTOR: F.L.A. = 0.7	
DIMENSIONS & WEIGHT	ELECTRICAL	DIMENSIONS & WEIGHT	ELECTRICAL
1'–10"L x 1'–11"W x 11"H 61.6LBS.	BLOWER: 208/1/60 0.53 F.L.A.	3'–1"L x 1'–6"H x 2'–1"W 159 LBS.	208/230 V 60 HZ 1 PH

LBNL STANDARD

DUCT–FREE MULTI SPLIT AC UNIT SCHEDULE

UNIVERSITY OF CALIFORNIA LAWRENCE BERKELEY NATIONAL LABORATORY

FACILITIES DIVISION

DRAWN BY | DATE
CHECKED BY
APPROVED BY
CAD FILE PATH
SCALE NTS
DRAWING NO. SCH103
PROJECT NO.
SHEET

T:\groups\ELECT\Romy\Mech_IHEM\Standard_Schedules\SCH103 DUCT–FREE–MULTISPLIT–SCHED.dwg